
BE29H-01



INSPECTION

w/ Mirror heater:

INSPECT MIRROR DEFOGGER OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 5 and the negative (-) lead to terminal 4.
- (b) Check that the mirror becomes warm.

HINT:

It will take a short time for the mirror to become warm.