

# 3. Canister

## A: REMOVAL AND INSTALLATION

- 1) Lift-up the vehicle.
- 2) Disconnect evaporation hoses from canister.




3) Remove canister from body.



4) Install in the reverse order of removal.

#### Tightening torque:


22.5±7 N·m (2.3±0.7 kg-m, 16.6±5.1 ft-lb)




# 4. Purge Control Solenoid Valve

### A: REMOVAL AND INSTALLATION

1) Disconnect battery ground cable.



2) Remove air cleaner case and air intake duct. <Ref. to 2-7 [W1A0].>



3) Remove bolt which installs purge control solenoid valve to intake manifold.

