BR102–02

INSTALLATION

Installation is in the reverse order of removal (See page BR–3).

HINT:

- After installation, fill the brake reservoir with brake fluid, bleed brake system (See Pub. No. RM339E on page BR–9).
- Check for leaks.